यस वीर अस्पतालको लागि आवश्यक सामानहरुको दररेट ३ (तिन) दिन भित्र पेश गर्नु हुन सम्बन्धित कम्पनी/फर्म/सप्लायर्सलाई आदेशानुसार अनुरोध गरिन्छ ।

Nepal Government Ministry of Health & Population National Academy of Medical Science

Bir Hospital

Kathmandu

Bill of Quantity

Т

Project: Civil Works for NAMS, Bir Hospital Site: Bir Hospital, Kathmandu

- **C**

S.N.	Description of Work	Quantity	Unit	Rate Rs.	Amount (NRs.)	Remarks
1	Site clear before and after construction as per site requirement.	1.00	job			
1	Dismantling Works					
1.1	Dismantling of Existing inside and outside wall etc and site clearance all complete as per instruction.	17.91	cu.m			
2	Dismantling of PCC Work.	0.18	cu.m			
3	Brick Work					
	Providing and laying brick masonry work in 1:6 cement sand ratio.	2.59	cu.m			
4	Supplying and fitting of 10mm plyboard for exterior and interior wall boothside and all work complete as per instruction of site engineer.	85.34	sq.m			
5	Finishing Work					
	Cement Plaster Work					
	Cement plastering on walls in 1:4 cement mortar	93.75	sq.m			
6	Painting Work					
	Two coate of emulsion paint with one coat of primer over clean surface.	288.80	sq.m			
	(Asian paint/ Jenson & Nicolson or equivalent)					
7	Applying of 2mm thick wall putty.	9.00	sq.m			
			Sub total			
			13% Vat			
	la Mordo:		G	Grand Total		

In Words:

Signature of Contractor:

Name of Contractor:

बिस्तृत जानकारीका लागि यस अस्पतालको वेभसाईट www.nams.org.np अथवा अस्पतालको खरिद इकाईमा सम्पर्क राख्न अनुरोध गरिन्छ ।